Forms Removing:- Forms not to be removed within fifteen days after concrete has been poured, except upon approval of Consulting Engineer.

Floors Ground:- All ground floors to have a concrete base. The finished floor surfaces to be concrete.

Floor Drains:- Floor to be finished level, except the two drained areas, unless otherwise specified.

Trenches:- Provide pipe trenches with removable covers, where and as shown.

Care Placing Concrete:- Care to be taken not to disturb any pipes or conduits installed by other contractors in placing the concrete base slab.

Concrete Floors-Ground:-Pipe and Drains:- Cast iron floor drains and drain pipe to be installed by plumbing contractor.

Floor Surface:- The dirt floor base of the rooms to be thoroughly tamped and graded six inches below the finished floor surface, and left free from soft pits and fills, and kept flooded for two days before depositing concrete.

Concrete not to be deposited until after all windows have been glazed and roof made tight.

Grooves and Expansion Joints:- No grooves or expansion joints to be provided in the floor.

Base Slab Concrete:- The five inch concrete base slab to consist of a 1:3:6 mixture. The gravel to pass through a